Third Street Road / St. Andrews Church Road Prioritization Matrix

	Corridor	Current LOS AM (PM)**	Projected LOS AM (PM)**	D,R,U,C Cost Est.	ROW needed	Need for Safety Improvements	Public Concern	Qk4 Priority	Qk4 Ranking	Project Description
	3rd St. Rd.									
	Intersections									
1	**1) 3rd St. Rd. @ Stonestreet Rd.**	C (C)								Level of Service evaluation and safety conditions meet current acceptable standards
2	**2) 3rd St. Rd. @ E. Pages Ln.**	B (E)	B (C)	$54,000	0.04	High	Low	High	5	Access Control, Channelization, landscaping, RTL from SB E. Pages to WB 3rd St.
3	**3) 3rd St. Rd. @ Arnoldtown Rd.**	B (D)	B (C)	$88,000	0.03	Low	Med	Med	11	Add RTL for SB Arnoldtown Rd to WB 3rd St.
4	**4) 3rd St. Rd. @ W. Manslick Rd.**	E (F)*	E (F)*	$44,000	0.02	Low	Low	Low	16	Eliminate skewed intersection; remove island and restripe
5	**5) 3rd St. Rd. @ Outer Loop**	B (C)								Level of Service evaluation and safety conditions meet current acceptable standards
6	**6) 3rd St. Rd. @ Wisertown Rd.**	B (C)*	B (C)*	$463,000	<1.0	Low	Med	Med	9	Widen and add turn lanes from Wisertown to 3rd St. Rd., widen 3rd St. Rd. to 3 lanes
7	**7) 3rd St. Rd. @ McNair Rd.**	B (C)*								Level of Service evaluation and safety conditions meet current acceptable standards
8	**8) 3rd St. Rd.@ Newcut Rd.**	D (F)	C (F)	$217,000	0.12	High	High	Med	10	Add right turn lanes on New Cut Rd.
	Corridor Improvements									
16	**James Hill Curve Raised Pavement Markings**	N/A	N/A	$138,000	N/A	High	High	High	2	Improve drainage, install raised pavement markings and signage to increase safety
17	**James Hill Curve Redesign**	N/A	N/A	$1 M	Req.	High	High	High	8	Redesign vertical and horizontal curve deficiencies to increase drainage and safety at this area
18	**Johnson's Day Care Entrance Revisions**	N/A	N/A	$33,000	N/A	High	High	High	1	Add bus only entrance and make improvements to existing entrance
	St. Andrews Church Rd.									
	Intersections									
10	**10) St. Andrews Church Rd. @ Arnoldtown Rd.**	C (C)	B (C)	1.5M	0.5	High	High	High	7	Widen St. Andrews Church Road to 3 lanes, add turn lanes on Arnoldtown Road
11	**11) St. Andrews Church Rd. @ St. Anthony Church Rd.**	D (F)*	B (C)						6	Widen St. Andrews Church Rd to 3 lanes, add signal and turn lanes on St. Anthony Church Road
12	**12) St. Andrews Church Rd. @ Blanton Ln.**	B (C)								Level of Service evaluation and safety conditions meet current acceptable standards
13	**13) St. Andrews Church Rd. @ Palatka Rd.**	B (C)	B (C)	$20,000	0.02	High	Low	Low	14	Define shopping center entrances with better access management, striping, and signage
	Corridor Improvements									
19	**Widen Curve at Doss HS**	N/A	N/A	$233,000	Req.	Low	Low	Med	12	Widen through curve for middle turn lane
	Palatka Rd.									
	Intersections									
9	**9) Palatka Rd. @ Southside Dr.**	B (C)								Level of Service evaluation and safety conditions meet current acceptable standards
	Corridor Improvements									
20	**Palatka Curve Raised Pavement Markings**	N/A	N/A	$50,000	N/A	High	Med	High	4	Install raised pavement markings and signage to increase safety from (MP 0.94) to (MP 1.4)
22	**Southside Dr. Safety Improvements**	N/A	N/A	$10,000		High	High	High	3	Install guardrails on both sides of the roadway at the culvert headwalls at (MP 6.65)
	New Cut Rd.									
	Intersections									
14	**14) New Cut Rd.@ Palatka Rd.**	F (F)	F (E)	$1 M	Relo)	High	Med	Low	17	Add right turn lane from southbound New Cut Rd to westbound Palatka Road
15	**15) Outer Loop @ New Cut Rd.**	C (D)	C (D)	$500,000	N/A	Med	Med	Low	15	Add RTL from EB Outer Loop to SB New Cut and widen bridge over Pond Creek
	Corridor Improvements									
21	**School Zone Consolidation**	N/A	N/A	<$20,000	N/A	Med	Low	Low	13	Revise school zone signage on New Cut Road per current MUTCD
								High		
								Med		
								Low		
	** LOS based on 2008 traffic volumes							Currently Acceptable		
	* Unsignalized intersections do not have a LOS assigned to the overall intersection, but to each movement itself. LOS shown is of the worst movement at these intersections.									

Third Street Road / St. Andrews Church Road Prioritization Matrix

Corridor	Construction Cost Est.	ROW needed	Need for Safety Improvements	Public Concern	Qk4 Priority	Qk4 Ranking	Project Description
3rd St. Rd.							
Sidewalks and Drainage							
Phase 1 Sidewalks and Drainage	$753,000.00	Req.	High	High	High	2	Improvements from Outer Loop (MP 4.66) to Christland Road (MP 5.80)
Phase 2 Sidewalks and Drainage	$1,373,000.00	Req.	High	High	Med	4	Just south of Stonestreet Road (MP 1.9) to Arnoldtown Road (MP 3.994)
Phase 3 Sidewalks and Drainage	$1,700,000.00	Req.	High	High	Low	9	Arnoldtown Road (MP 3.994) to the Outer Loop (MP 4.66)
St. Andrews Church Rd.							
Sidewalks							
Phase 1 Sidewalks	$71,000.00	Req.	High	High	High	1	Windmere Dr. (MP 5.19) to Palatka Road (MP 5.486)
Phase 2 Sidewalks	$72,000.00	Req.	High	High	Med	5	Arnoldtown Road (MP 4.119) to Blanton Lane (MP 4.419)
Phase 3 Sidewalks	$231,000.00	Req.	High	High	Low	8	Dixie Highway (MP 3.148) to Arnoldtown Road (MP 4.119)
Palatka Rd.							
Sidewalks							
Phase 1 Sidewalks	$42,000.00	Req.	High	High	High	3	St. Andrews Church Road (MP 0) to Iroquois Park Road (MP 0.176)
Phase 2 Sidewalks	$194,000.00	Req.	High	High	Med	6	Iroquois Park Road (MP 0.176) to Park Road (MP 0.991)
Phase 3 Sidewalks	$69,000.00	Req.	High	High	Low	7	New Cut Road (MP 1.446) to Southside Drive (MP 1.736)
			High				
			Med				
			Low				